

Subdivisions, T. 1 N., R. 35 E.

Chains

No timber, except a bunch of pine. Mountainous lands,
55.37 chs.

June 26th, 1895.

General Description

This township is on the Blue Mountains and near their summit. The land is undulating hills in the southern part; the hollows growing into deep and precipitous canyons in the northern part. The altitude is too great for agriculture, therefore the lands are chiefly valuable for grazing purposes. This township is well watered by springs and streams. There is some valuable timber yet remaining, but it is fast disappearing before wood and tie choppers.

Note. In the survey of the subdivisions of this township, I could not make my work agree with the running of the U.I.R. line as given in the notes furnished me by the Surveyor General; neither did the Dept. who surveyed on the W. side of the bdy. line. As our work practically agrees, I think the U.I.R. bdy. line must be crooked.

(Signed) M. Buchanan,
U.S.Dept. Surveyor.

Note 2nd. Although not in limits as to dist. on line bet. secs. 27 and 34, my line practically agrees with that previously run bet. secs. 27 and 28. I could not be within limits on both lines. I find similar conditions at other points.

(Signed) Manius Buchanan
U.S.Dept. Surveyor

Field Notes of the Survey of the Corrections of
Subdivision Lines of T.1 N., R. 35 E., as surveyed
by Manius Buchanan, under his contract No. 635,
dated April 19th, 1895.

I go to the cor. of secs. 34, 35, 2 & 3 on Base line R.35
E. Here, I find a tamarac post 5 ins. square set firmly
in the ground, from which

A pine 25 ins. in diam. bears N. 35° E. 86 lks. dist.,
marked T.1 N.R. 35 E. S.35 B.T., and

An alder 5 ins. in diam. bears S.39° E. 20½ lks. dist.,
marked T.1 S.R. 35 E. S. 2 B.T.