

Base Line of T. 1 N., R. 36 E.
 Surveyed by Timothy W. Davenport under contract No. 102.
 Dated July 20, 1863.

| | | |
|--------|---|-------|
| Chains | Thence East on South boundary of sec. 31. Var. 20°30'E. | |
| 40.00 | Set qr. sec. post, from which, A hemlock, 16 ins. in diam., bears N.60°W., 17 lks. dist. A hemlock, 10 ins. in diam., bears N.25°E., 35 lks. dist. | -40 |
| 80.00 | Set post corner to secs. 31 and 32, from which, A red fir, 12 ins. in diam., bears N.20°E., 114 lks. dist. A red fir, 20 ins. in diam., bears N.85°W., 74 lks. dist. Var. 18°30'E. Surface broken by knobs. Timber scattered. | +100 |
| | Thence East on South boundary of sec. 32. Var. 18°30'E. | |
| 38.00 | Bottom of slope. | -1200 |
| 40.00 | Set qr. sec. post on the West bank of a dry creek, 50 lks. wide, runs South, from which post, A red fir, 8 ins. in diam., bears S.40°W., 34 lks. dist. A red fir, 6 ins. in diam., bears N.60°E., 11 lks. dist. | |
| 59.00 | Top of sharp ridge, course N. and S. | +1200 |
| 80.00 | Set post corner to secs. 32 and 33, from which, A pine, 40 ins. in diam., bears N.10°E., 50 lks. dist. A pine, 36 ins. in diam., bears S.45°W., 150 lks. dist. Var. 21°East. | -400 |
| | Thence East on South boundary of sec. 33. Var. 21° E. | |
| 40.00 | Set qr. sec. post on bald stoney hill. Made mound of rock. | |