

Base Line of T. 1 N., R. 36 E.

Chains 80.00	Set post corner to secs. 33 and 34, from which, A pine, 36 ins. in diam., bears N.60°E., 386 lks. dist. A pine, 16 ins. in diam., bears N.52°W., 330 lks. dist. Var. 21°10'East.	+15
	Thence East on South boundary of sec. 34. Var. 21°10'E.	
40.00	Set qr. sec. post, from which, A hemlock, 6 ins. in diam., bears N.10°E., 5 lks. dist. " " 14 " " " " N.20°W., 10 " "	-700
80.00	Set post corner to secs. 34 and 35, made mound of rock on the East side of awful furrow in the mountain. August 10.	-300
	Thence East on South boundary of sec. 35. Var. unobtained.	
24.00	Bottom of slope, and intersect creek 75 lks. wide, running North.	-800
32.00	Leave bottom and commence to ascend.	
40.00	Set qr. sec. post on side of gorge, made mound of rock.	+500
80.00	Set post corner to secs. 35 and 36, on South side of Spur of mountain, course West. Var. 22°30'East.	+900
	East on South boundary of sec. 36. Var. 22°30'E.	
40.00	Set qr. sec. post on top of table land in edge of Timber, from which post, A tamarack, 6 ins. in diam., bears N.40°W., 25 lks. " " 16 " " " " S.50°W., 40 "	+600
80.00	Set post corner to secs. 36 and 31, Township 1 North, Ranges 36 and 37 East, from which, A hemlock, 14 ins. in diam., bears N.10°E., 46 lks. dist. " " 12 " " " " N.20°W., 22 " " " " 10 " " " " S.35°W., 26 " " Var. 21°30'East. Surface flat; Timber thick and green.	+300