

## Resurvey of the Base Line through Range 36 East.

Chains	
	<p>A pine, 24 ins. in diam., bears N.45°E., 67 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p> <p>A fir, 30 ins. diam., bears South 17 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p> <p>The old <math>\frac{1}{4}</math> sec. cor., a post bears W., 11.00 chs. dist., I destroy same and obliterate the marks on old bearing trees, 2 firs.</p>
49.00	Foot of hill about 1100 ft. below last sec. cor., course N.
50.00	Dry bed of Meacham Creek, 100 lks. wide, course S.
52.50	Wagon road, course N.
53.50	Ascend about 1100 ft. to
80.00	<p>Set a basalt stone, 24x10x4 ins., 18 ins. in the ground, for cor. to secs. 31 and 32, marked B L with 5 notches on E. and 1 notch on W. edges, from which</p> <p>A pine, 34 ins. diam., bears S.80°W., 63 lks. dist., marked T 1 S R 36 E S 6 B T.</p> <p>A pine, 12 ins. diam., bears N.40°W., 154 lks. dist., marked T 1 N R 36 E S 31 B T.</p> <p>The old sec. cor. a post, bears W., 12.25 chs. dist. I destroy same and obliterate marks on old bearing trees.</p> <p>Land, mountainous.</p> <p>Soil, stony, 3rd rate.</p> <p>Timber, scattering pine, fir and tamarack.</p>
	<p>West on Base Line on S. boundary of sec. 31.</p> <p style="text-align: center;">Var. 21°E.</p> <p>Ascend about 200 ft. to</p>
11.50	Top of hill, course N. and S.
40.00	<p>Set a basalt stone, 16x12x4 ins., 11 ins. in the ground, for <math>\frac{1}{4}</math> sec. cor. marked B L <math>\frac{1}{4}</math> on N. face, from which</p> <p>A fir, 12 ins. diam., bears N.50°W., 23 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p> <p>A pine, 6 ins. diam., bears S.10°E., 30 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p>