

North boundary of T. 1 N., R. 36 E.

Chains	
	<p>A pine, 22 ins. diam., bears S. 73° W., 58 lks. dist., marked $\frac{1}{4}$ S B T.</p>
41.00	<p>Bottom of gulch, about 350 ft. below last ridge, course S.W.</p>
48.62	<p>Enter creek bottom, course N.25°W.</p>
51.85	<p>Graded road bed of Baker City Railway line, course N.26°25'W.</p>
54.20	<p>Wagon road, course N. and S.</p>
60.40	<p>Meacham creek, 150 lks. wide, runs N.50°W.</p>
70.00	<p>Leave bottom and ascend hill, course N.W.</p>
80.00	<p>Set a post 4 ft. long, 4 ins. square, 24 ins. in the ground, for cor. to secs. 31 and 32, 5 and 6, marked T 2 N S 32 on N.E., T 1 N R 36 E S 5 on S.E., T 1 N R 36 E S 6 on S.W., and T 2 N R 36 E S 31 on N.W. faces, with 5 notches on E. and 1 notch on W. edges, from which,</p> <p>A fir, 26 ins. diam., bears N.70°E., 8 lks. dist., marked T 2 N R 36 E S 32 B T.</p> <p>A fir, 32 ins. diam., bears S.35°E., 9 lks. dist., marked T 1 N R 36 E S 5 B T.</p> <p>A pine, 30 ins. diam., bears S.33°W., 35 lks. dist., marked T 1 N R 36 E S 6 B T.</p> <p>A fir, 10 ins. diam., bears N.63°W., 12 lks. dist., marked T 2 N R 36 E S 31 B T.</p>
	<p>Land, mountainous. Soil, sandy loam and stony, 2nd and 3rd rate. Timber, scattering pine, fir and tamarack. Dense undergrowth of pine, fir, tamarack and buck brush.</p>
	<p>N.89°39'W. on a true line between secs. 6 and 31. Var. 17°30'E.</p>
	<p>Ascend about 200 ft. to</p>
7.50	<p>Top of ridge, course N.E.</p>
	<p>Descend about 600 ft. to</p>
22.00	<p>Ravine, course N.E.</p>
	<p>Ascend about 600 ft. to</p>