

Subdivisions of T. 1 N., R. 36 E.

Chains	<p>Land, mountainous.</p> <p>Soil, 2nd rate.</p> <p>Heavily timbered with fir, pine and tamarack on N. 35.00 chs.</p> <p>Dense undergrowth of Buck brush on entire mile.</p>
	<p>East on a random line between secs. 25 and 36.</p> <p style="text-align: center;">Var. 22°E.</p> <p>Ascend along steep hillside.</p> <p>40.00 Set temporary $\frac{1}{4}$ sec. cor.</p> <p>80.62 Intersect E. boundary, 40 lks. S. of the cor. to secs. 25, 36, 30 and 31, which is a post 4 ins. square marked T 1 N S 30 on N.E., R 37 E S 31 on S.E., R 36 E S 36 on S.W., and S 25 on N.W. faces with 1 notch on S. and 5 notches on N. edges, from which,</p> <p style="padding-left: 40px;">A pine, 24 ins. diam., bears N.5°W., 360 lks. dist., marked T 1 N R 36 E S 26 B T.</p> <p style="padding-left: 40px;">and mound of stone around post.</p> <p>Thence I run.</p> <p>S.89°43'W. on a true line between secs. 25 and 36.</p>
40.31	<p>Set a basalt stone, 14x12x4 ins., 9 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, from which,</p> <p style="padding-left: 40px;">A fir, 30 ins. diam., bears N.10°E., 248 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p style="padding-left: 40px;">A fir, 7 ins. diam., bears S.5°W., 55 lks. dist., marked $\frac{1}{4}$ S B T.</p>
80.62	<p>The cor. to secs. 25, 26, 35 and 36.</p> <p>Land, mountainous.</p> <p>Soil, stony, 3rd rate.</p> <p>Heavily timbered with fir, tamarack and pine.</p>
	<p>North between secs. 25 and 26.</p> <p style="text-align: center;">Var. 22°E.</p> <p>Descend about 250 ft. to</p>
21.00	<p>North fork of Meacham creek, 30 lks. wide, flows S.W.</p>
22.00	<p>Leave heavy and enter scattering timber.</p>