

## Subdivisions of T. 1 N., R. 36 E.

Chains	<p>East on a random line between secs. 26 and 35.</p> <p style="text-align: center;">Var. <math>22\frac{1}{2}^{\circ}</math>E.</p> <p>Ascend about 300 ft. to</p> <p>22.00 Top of ridge, course S.W.</p> <p>40.00 Set temporary <math>\frac{1}{4}</math> sec. cor.</p> <p>59.00 Bottom of gulch about 400 ft. below ridge. Meacham creek, 50 lks. wide, runs S.W.</p> <p>80.42 Intersect 30 lks. N. of the cor. to secs. 25, 26, 35 and 36.</p> <p>Thence I run</p> <p>N. <math>89^{\circ}47'</math>W. on a true line between secs. 26 and 35.</p> <p>40.21 Set a basalt stone, 12x10x5 ins., 8 ins. in the ground, for <math>\frac{1}{4}</math> sec. cor. marked <math>\frac{1}{4}</math> on N. face, from which</p> <p style="padding-left: 40px;">A fir, 8 ins. diam., bears N. <math>75^{\circ}</math>W., 75 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p> <p style="padding-left: 40px;">A pine, 14 ins. diam., bears S. <math>40^{\circ}</math>W., 63 lks. dist., marked <math>\frac{1}{4}</math> S B.T.</p> <p>80.42 The cor. to secs. 26, 27, 34 and 35.</p> <p>Land, mountainous.</p> <p>Soil, sandy loam and stony, 2nd and 3rd rate.</p> <p>Heavily timbered with fir, pine and tamarack.</p>
	<p>North between secs. 26 and 27.</p> <p style="text-align: center;">Var. <math>22\frac{1}{2}^{\circ}</math>E.</p> <p>Ascend along side hill.</p> <p>40.00 Set a basalt stone, 13x9x6 ins., 9 ins. in the ground, for <math>\frac{1}{4}</math> sec. cor. marked <math>\frac{1}{4}</math> on W. face, and raised a mound of stone alongside.</p> <p>80.00 Set a basalt stone, 16x10x8 ins., 11 ins. in the ground, for cor. to secs. 22, 23, 26 and 27 marked with 2 notches on S. and E. edges, from which,</p> <p style="padding-left: 40px;">A pine, 28 ins. diam., bears S. <math>60^{\circ}</math>W., 200 lks. dist., marked T 1 N R 36 E S 27 B T.</p> <p style="padding-left: 40px;">A pine, 12 ins. diam., bears N. <math>35^{\circ}</math> W., 192 lks. dist., marked T 1 N R 36 E S 22 B T.</p> <p>No other tree within limits.</p>