

Subdivisions of T. 1 N., R. 36 E.

Chains	
	<p>Land, mountainous.</p> <p>Soil, 2nd rate.</p> <p>Timber, scattering fir and pine with dense undergrowth of mountain laurel and wild cherry.</p>
	<p>East on a random line between secs. 14 and 23.</p> <p style="text-align: center;">Var. $19\frac{1}{4}^{\circ}$E.</p> <p>Ascend about 500 ft. to</p> <p>27.00 Top of mountain, course S.</p> <p>40.00 Set temporary $\frac{1}{4}$ sec. cor.</p> <p>80.66 Intersect 10 lks. N. of the cor. to secs. 13, 14, 23 and 24.</p>
	<p>Thence I run</p> <p>N. $89^{\circ}56'$W. on a true line between secs. 14 and 23.</p> <p>40.33 Set a basalt stone, 16x10x4 ins., 11 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone alongside.</p>
	<p>80.66 The cor. to secs. 14, 15, 22 and 23.</p> <p>Land, mountainous.</p> <p>Soil, 2nd rate.</p> <p>Timber, scattering fir and pine with dense undergrowth of mountain laurel and wild cherry.</p>
	<p>North between secs. 14 and 15.</p> <p style="text-align: center;">Var. $19\frac{1}{4}^{\circ}$E.</p> <p>2.00 Bottom of gulch about 25 ft. below cor., course S.W.</p> <p>Ascend.</p> <p>40.00 Set a basalt stone, 12x11x5 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face and raised a mound of stone alongside.</p> <p>80.00 Set a basalt stone, 17x11x8 ins., 11 ins. in the ground,</p>