

Subdivisions of T. 1 N., R. 36 E.

Chains	
	<p>for cor. to secs. 10, 11, 14 and 15 marked with 4 notches on S. and 2 notches on E. edges, and raised a mound of stone alongside.</p> <p>Land, mountainous.</p> <p>Soil, sandy loam, 2nd rate.</p> <p>Timber, scattering fir, pine and tamarack with dense undergrowth of mountain laurel and wild cherry.</p>
<p>6.00</p> <p>40.00</p> <p>80.30</p> <p>40.15</p> <p>80.30</p>	<p>East on a random line between secs. 11 and 14.</p> <p style="text-align: center;">Var. 21 3/4° E.</p> <p>Ascend about 50 ft. to</p> <p>Top of ridge, course N.</p> <p>Set temporary 1/4 sec. cor.</p> <p>Intersect 32 lks. S. of the cor. to secs. 11, 12, 13 and 14.</p> <p>Thence I run</p> <p>S. 89°46'W. on a true line between secs. 11 and 14.</p> <p>Set a basalt stone, 12x10x5 ins., 8 ins. in the ground, for 1/4 sec. cor. marked 1/4 on N. face, and raised a mound of stone alongside.</p> <p>The cor. to secs. 10, 11, 14 and 15.</p>
	<p>Land, mountainous.</p> <p>Soil, 2nd rate.</p> <p>Timber, scattering pine, fir and tamarack with dense undergrowth of wild cherry and mountain laurel.</p>
	<p>North between secs. 10 and 11.</p> <p style="text-align: center;">Var. 21 3/4° E.</p>