

## Subdivisions of T. 1 N., R. 36 E.

Chains	
	A fir, 6 ins. diam., bears N.40°E., 48 lks. dist., marked $\frac{1}{4}$ S B T.
	A fir, 5 ins. diam., bears S.70°W., 35 lks. dist., marked $\frac{1}{4}$ S B T.
63.50	Bottom of gulch about 700 ft. below last sec. cor., course E.
80.00	A point about 250 ft. above gulch. Set a basalt stone, 16x8x6 ins., 11 ins. in the ground, for cor. to secs. 27, 28, 33 and 34, marked with 1 notch on S and 3 notches on E. edges, and raised a mound of stone alongside.
	Land, mountainous.
	Soil, 2nd rate.
	Timber, scattering fir, pine and tamarack with dense undergrowth of mountain laurel, wild cherry and buck brush.
East on a random line between secs. 27 and 34.	
Var. $21\frac{1}{4}$ °E.	
	Descend about 300 ft. to
25.50	Bottom of gulch, course N.E.
37.00	Top of ridge, about 150 ft. above gulch, course N.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
57.00	Foot of hill about 250 ft. below ridge, N.
59.25	Graded road bed of the Baker City branch of the O.R. and N. Cos. Railway line, course N.
60.50	Meacham creek, 50 lks. wide, flows N.
64.00	A saw mill bears N. 4.00 chs. dist.
67.25	Wagon Road, course N.
69.00	Foot of hill, course N.
	Ascend.
80.40	Intersect 50 lks. N. of the cor. to secs. 26, 27, 34 and 35.
	Thence I run N.89°39'W. on a true line between secs. 27 and 34.