

Subdivisions of T. 1 N., R. 36 E.

Chains	Descend.
40.00	Set a basalt stone, 14x9x6 ins., 9 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, from which, A fir, 12 ins. diam., bears N.65°E., 18 lks. dist., marked $\frac{1}{4}$ S B.T. A fir, 15 ins. diam., bears N.40°W., 11 lks. dist., marked $\frac{1}{4}$ S B T.
40.50	Bottom of gulch about 500 ft. below sec. cor., course E.; a creek, 10 lks. wide, runs E.
70.00	Top of ridge about 400 ft. above creek, course E. Descend about 200 ft. to
80.00	Set a basalt stone, 15x6x6 ins., 10 ins. in the ground, for cor. to secs. 8, 9, 16 and 17, marked with 4 notches on S. and E. edges, from which, A fir, 6 ins. diam., bears N.45° E., 88 lks. dist., marked T 1 N R 36 E S 9 B T. A fir, 8 ins. diam., bears S.10°E., 68 lks. dist., marked T 1 N R 36 E S 16 B T. A fir, 6 ins. diam., bears S.80°W., 60 lks. dist., marked T 1 N R 36 E S 17 B T. A fir, 5 ins. diam., bears N.30°W., 36 lks. dist., marked T 1 N R 36 E S 8 B T.
	Land, mountainous.
	Soil, stony, 3rd rate.
	Timber, scattering fir, pine and tamarack.
	September 19, 1882.
	East on a random line between secs. 9 and 16.
	Var. 22°E.
12.00	Foot of hill about 150 ft. below cor., course N.W.
15.50	Wagon road, course N.W.
20.58	Graded road bed for Baker City Railway, course N.W.
22.50	Meacham creek, 75 lks. wide, course N.W.
	Ascend.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
56.00	Top of ridge about 100 ft. above creek, course S.W.