

Subdivisions of T. 1 N., R. 36 E.

Chains	Descend about 75 ft. to
70.00	Dry bed of creek, course S.W.
80.44	Intersect 15. lks. S. of the cor. to secs. 9, 10, 15 and 16.
	Thence I run.
	S.89°54'W. on a true line between secs. 9 and 16.
40.22	Set a basalt stone, 17x6x5 ins., 11 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, from which,
	A pine, 5 ins. diam., bears N.80°W., 46 lks. dist., marked $\frac{1}{4}$ S B T.
	A pine, 18 ins. diam., bears S.20°E., 73 lks. dist., marked $\frac{1}{4}$ S B T.
80.44	The cor. to secs. 8, 9, 16 and 17.
	Land, mountainous.
	Soil, sandy loam and stony, 2nd and 3rd rate.
	Timber, scattering pine and fir.
	North between secs. 8 and 9.
	Var. 22°E.
	Descend about 75 ft. to
3.00	Bottom of gulch, course E.
10.00	Top of ridge about 75 ft. above gulch, course E.
39.00	Wilbur's house bears E., 9.50 chs. dist.
40.00	Set a basalt stone, 20x9x5 ins., 15 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, from which,
	A fir, 6 ins. diam., bears S.20°E., 94 lks. dist., marked $\frac{1}{4}$ S B T.
	A pine, 30 ins. diam., bears N.5°W., 142 lks. dist., marked $\frac{1}{4}$ S B T.
67.00	Meacham creek, 100 lks. wide, course N.W.
76.00	Wagon road, course N.W.
80.00	Set a post 4 ft. long, 4 ins. square, 24 ins. in the ground, for cor. to secs. 4, 5, 8 and 9 marked T 1 N S 4 on N.E., R 36 E S 9 on S.E., S 8 on S.W., and S 5 on N.W. faces, with 5 notches on S. and 4 notches on E. edges, from which,