

## Subdivisions of T. 1 N., R. 36 E.

Chains 80.64	Intersect 55 lks. S. of the cor. to secs. 8, 9, 16 and 17.  Thence I run S.89°36'W. on a true line between secs. 8 and 17.
40.32	Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on N. face, from which,  A fir, 12 ins. diam., bears N.5°W., 12 lks. dist., marked $\frac{1}{4}$ S B T.  A fir, 10 ins. diam., bears S.20°E., 6 lks. dist., marked $\frac{1}{4}$ S B T.
80.64	The cor. to secs. 7, 8, 17 and 18.  Land, mountainous.  Soil, sandy loam, 2nd rate.  Timber, scattering fir and pine with dense undergrowth of wild cherry and buck brush.  September 22, 1882.
	West on a random line between secs. 7 and 18.  Var. $21\frac{1}{4}$ °E.  Ascend about 200 ft. to
28.00	Top of ridge, course N.E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
45.00	Bottom of gulch about 150 ft. below ridge, course N.
52.00	Top of ridge about 75 ft. above gulch, course N.
90.20	Intersect W. boundary, 56 lks. S. of the cor. to secs. 7, 18, 12 and 13, which is a post 4 ins. square, marked T 1 N S 7 on N.E., R 36 E S 18 on S.E., R 35 E S 13 on S.W., and S 12 on N.W. faces, with 4 notches on S. and 2 notches on N. edges, and a mound of stone around post.  Thence I run. S.89°38'E. on a true line between secs. 7 and 18.
50.20	Set a basalt stone, 14x12x6 ins., 9 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face and raised a mound of stone alongside.
90.20	The cor. to secs. 7, 8, 17 and 18.