

Subdivisions of T. 1 N., R. 36 E.

Chains	<p>Land, mountainous.</p> <p>Soil, stony, 3rd rate.</p> <p>Timber, scattering pine, fir and tamarack, with dense undergrowth of wild cherry and buck brush.</p>
	<p>North between secs. 7 and 8.</p> <p style="text-align: right;">Var. $21\frac{1}{2}^{\circ}$ E.</p> <p>Through timber and brush.</p>
22.00	Descend steep hill.
40.00	Set a basalt stone, 14x10x8 ins., 9 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone alongside.
59.00	Bottom of gulch about 1000 ft. deep, course N.E. Ascend about 500 ft. to
80.00	Set a basalt stone, 20x10x8 ins., 15 ins. in the ground, for cor. to secs. 5, 6, 7 and 8, marked 5 notches on S. and E. edges, and raised a mound of stone alongside.
	<p>Land, mountainous.</p> <p>Soil, stony, 3rd rate.</p> <p>Timber, scattering fir and pine with dense undergrowth of fir, pine and buck brush.</p>
	<p>East on a random line between secs. 5 and 8.</p> <p style="text-align: right;">Var. $19\frac{3}{4}^{\circ}$ E.</p> <p>Descend about 500 ft. to</p>
28.00	Bottom of gulch, course N.E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
44.00	Top of ridge about 250 ft. above gulch, course N.E. Descend about 200 ft. to
57.00	A spring branch, 2 lks. wide, runs. N.E. Ascend about 100 ft. to
65.00	Top of ridge, course N. Descend about 125 ft. to
71.00	Meacham creek, 50 lks. wide, course N.
77.50	Wagon road, course N.
80.22	Intersect 15 lks. S. of the cor. to secs. 4, 5, 8 and 9.