

Subdivisions of T. 1 N., R. 36 E.

Chains

General Description

The land in this township is all rough and mountainous with the exception of a small strip from 10 to 20 chs. in width along Meacham creek. The soil along Meacham creek is mostly a fair quality of 2nd rate, and the soil on the mountainous part is mostly 3rd rate, part of it being very stony. The entire township is covered with scattering fir, pine and tamarack timber. The timber is of good quality but is not abundant enough to be of much importance. The Baker City branch of the Oregon Railway and Navigation Co's. line is at present being constructed along the Meacham creek canyon in this township. There is one settler each in secs. 9 and 34, and a sawmill in sec. 27.

Exterior Line of T. 1 N., R. 37 E.
 Surveyed by Jacob C. Cooper, contract No. 397.
 Dated July 1, 1881.

(West Boundary)

From the Base Line cor. to Tps. 1 N., Rs. 36 and 37 E., which is a post $1\frac{1}{2}$ ft. long, 3 ins. square marked T 1 N R 37 E S 31 on N.E., R 36 E S 36 on N.W. faces with 6 notches on the N. E. and W. edges.

A hemlock, 14 ins. diam., bears N.10°E., 36 lks. dist., marked T 1 N R 37 E S 31 B T.

A hemlock, 12 ins. diam., bears N.20°W., 22 lks. dist., marked T 1 N R 36 E S 36 B T.

A hemlock, 10 ins. diam., bears S.35°W., 26 lks. dist., marked T 1 S R 36 E S 1 B T.

I run

North between secs. 31 and 36.

Var. 21°E.

Descend through fir and tamarack timber.

40.00 Set post 3 ft. long, 3 ins. square, 18 ins. in the ground, on steep mountain side sloping E. 2000 ft. above creek N. and 400 ft. below the summit in scattering fir timber with dense undergrowth for $\frac{1}{4}$ sec. cor. marked