

West Boundary of T. 1 N., R. 37 E.

Chains	
	<p>$\frac{1}{4}$ S on E. and W. faces, from which,</p> <p>A fir, 14 ins. diam., bears S.74°E., 30 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>A fir, 16 ins. diam., bears S.52°W., 29 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p style="text-align: center;">Var. 20°E.</p>
51.00	Glade on mountain side.
75.00	Descend through timber and dense undergrowth.
80.00	<p>Set post 4 ft. long, 4 ins. square, 2 ft. in the ground, 100 ft. below the summit 1000 ft. above creek on open ridge on the S. side for cor. to secs. 25, 30, 31 and 36 marked T 1 N S 30 on N.E., R 37 E S 31 on S.E., R 36 E S 36 on S.W. and S 25 on the N.W. faces, with 1 notch on the S. and 5 notches on the N. edges, from which,</p> <p>A pine, 24 ins. diam., bears N.5°W., 360 lks. dist., marked T 1 N R 36 E S 25 B T.</p> <p>Land, high broken and mountainous.</p> <p>Soil, rocky, 4th rate.</p> <p>Timber, fir, pine and tamarack.</p>
	<p>N. between secs. 25 and 30.</p> <p style="text-align: center;">Var. 22°E.</p> <p>Descend through timber and dense undergrowth.</p>
36.50	Meacham creek, 75 lks. wide, course W.
40.00	<p>A thorn tree, 3 ins. diam., which I marked for $\frac{1}{4}$ sec. cor. $\frac{1}{4}$ S on the E. and W. faces, on the N. bank of the river in balm and fir timber. Dense underbrush.</p> <p>A balm, 28 ins. diam., bears S.80°W., 15 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>Latitude at noon 45°34'N.</p>
41.50	Ascend through open pine timber.
56.00	Summit of rocky ridge, course N.W.
80.00	<p>4 flat stones, 14x 14 ins., laid flat ways on top of each other on steep ridge of canyon facing E., 40 ft. above bottom of canyon, which I marked X on top and T 1 N S</p>