

West Boundary of T. 1 N., R. 37 E.

Chains	<p>A leaning alder, 2 ins. diam., bears S.45°W., 4 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>Var. 22°15'E.</p> <p>65.00 Spring branch, course W.</p> <p>80.00 Set post $4\frac{1}{2}$ ft. long, 4 ins. square, 2 ft. in the ground, on W. hillside in heavy timber with dense undergrowth, 100 ft. below the summit for cor. to Tps. 1 N. Rs. 36 and 37 E., marked T 2 N S 31 on N.E., R 37 E S 6 on S.E., T 1 N S 1 on the S.W., and R 36 E S 36 on the N.W. faces with 6 notches on each edge</p> <p>A fir, 18 ins. diam., bears N.32°E., 18 lks. dist., marked T 2 N R 37 E S 31 B T.</p> <p>A fir, 12 ins. diam., bears N.43°W., 75 lks. dist., marked T 2 N R 36 E S 36 B T.</p> <p>A fir, 20 ins. diam., bears S 51°W., 47 lks. dist., marked T 1 N R 36 E S 1 B T.</p> <p>A fir, 20 ins. diam., bears S.18°E., 23 lks. dist., marked T 1 N R 37 E S 6 B T.</p> <p>High table land.</p> <p>Soil, gravelly, 2nd rate.</p> <p>Timber, spruce, fir and tamarack.</p> <p>Sept. 16, 1881.</p>
	<p style="text-align: center;">General Description</p> <p>The Tps. on the E. of this line is a succession of deep, craggy canyons and high mountain peaks nearly barren. Grass is scarce.</p> <p>Timber is scarce and of inferior quality.</p> <p>Water is also scarce except in the deepest canyons.</p> <p>Meacham Creek heads in the N.E. corner of the Tps.</p> <p>Black bears are numerous.</p>