

South Boundary of T. 2 N., R. 37 E.

| Chains | |
|--------|---|
| | <p>Umatilla River and Meacham Creek. Post is 4 ft. long, $4\frac{1}{2}$ ins. square, 1 ft. in ground, marked for cor. to secs. 2, 3, 35 and 36. T 2 N S 35 on N.E., R 37 E S 2 on S.E., T 1 N S 3 on S.W., and S 34 on N.W. faces, with 2 notches on E. and 4 notches on West edges.</p> <p>A leaning fir, 26 ins. diam., bears S. 10°E., 1.36 lks. dist., marked T 1 N R 37 E S 2 B T.</p> <p>A fir, 12 ins. diam., bears N. 34°W., 70 lks. dist., marked T 2 N R 37 E S 34 B T.</p> <p>A fir, 16 ins. diam., bears S. 36°W., 92 lks. dist., marked T 1 N R 37 E S 3 B T.</p> <p>Land, mountainous, rough and broken.</p> <p>Soil, lava, gravelly and stony.</p> <p>Timber, fir, spruce and pine.</p> |
| | <p>N. $89^{\circ}58'$W. on true line between secs. 3 and 34.</p> <p style="text-align: center;">Var. $21^{\circ}30'$.</p> <p>Slight descent.</p> |
| 5.00 | Descend abruptly into rugged canyon. Use micrometer to 40.00 on opposite side of canyon. |
| 40.00 | <p>Set post $3\frac{1}{2}$ ft. long, 3 ins. square on East slope of Mt. in heavy fir timber. Post, 18 ins. in ground, marked $\frac{1}{4}$ S for $\frac{1}{4}$ sec. cor.</p> <p>A fir, 24 ins. diam., bears S. 8°W., 15 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>A fir, 24 ins. diam., bears N. 29°E., 16 lks. dist., marked $\frac{1}{4}$ S B T.</p> |
| 55.00 | <p>Summit of ridge, course N. and S., 900 ft. above bottom of canyon just passed.</p> <p>Descend.</p> <p style="text-align: center;">Var. $17^{\circ}30'$.</p> |
| 66.00 | <p>Bottom of ravine.</p> <p>Ascend.</p> |
| 80.00 | <p>Set post 4 ft. long, 4 ins. square, 1 ft. in ground, and raised mound of stone around its base, 3 ft. in diam., and $1\frac{1}{2}$ ft. high, for cor. to secs. 3, 4, 33 and 34, in</p> |