

South Boundary of T. 2 N., R. 37 E.

Chains	<p>A fir, 12 ins. diam., bears N.20°W., 48 lks. dist., marked T 2 R 37 E S 32 B T.</p> <p>Land, mountainous and broken.</p> <p>Soil, rocky and worthless, 4th rate, barren ridges.</p> <p>Timber, fir, pine and spruce.</p>
	<p>N.89°58'W. on a true line between secs. 5 and 32. Var. 24° E.</p>
	<p>Descend.</p>
2.00	<p>Fir timber and underbrush.</p>
8.00	<p>Glade, 1.50 chs. wide.</p>
11.00	<p>Ascend.</p>
15.00	<p>Summit of ridge, course N. and S. Descend through timber and undergrowth.</p>
19.00	<p>Enter glade, 2.50 chs. wide.</p>
30.00	<p>Spring branch, course N. Ascend abruptly.</p>
40.00	<p>Set post, 3½ ft. long, 3 ins. sq., marked ¼ S on N. and S. faces, for ¼ sec. cor., with mound of stone about the base of post, in center of glade, 1.00 chs. wide. Mound of stone, 3 ft. base, 18 ins. high.</p>
	<p>A fir, 36 ins. diam., bears N.46°E., 88 lks. dist., marked ¼ S B T.</p>
	<p>A pine, 24 ins. diam., bears S.82°W., 150 lks. dist., marked ¼ S B T.</p>
	<p>Var. 13°E.</p>
	<p>Descend.</p>
48.70	<p>Bottom of ravine, course N. Ascend through windfall.</p>
79.00	<p>Summit of ridge, course N. and S.</p>
80.00	<p>Set post, 4 ft. long, 4 ins. square, 2 ft. in ground, for cor. to secs. 5, 6, 31 and 32 on West slope in dense fir and spruce timber. Post is marked T 2 N S 32 on N.E., R 37 E S 5 on S.E., T 1 N S 6 on S.W. and S 31 on N.W. faces, with 5 notches on East and one notch on West edges.</p>