

## Resurvey of Base Line through Range 37 East

Chains	
	<p>A fir, 10 ins. diam., bears S.17°W., 26 lks. dist., marked T 1 S R 37 E S 5 B T.</p> <p>A tamarack, 14 ins. diam., bears N.40°W., 26 lks. dist., marked T 1 N R 37 E S 32 B T.</p> <p>The old sec. cor., a badly decayed post, bears W., 16.93 chs. dist. I destroy this post also the marks on old bearing trees, 3 tamaracks.</p> <p>Land, mountainous.</p> <p>Soil, sandy loam., 2nd rate.</p> <p>Heavily timbered with fir and tamarack. Dense undergrowth of young fir and tamarack.</p>
	<p>West on Base Line on S. boundary of sec. 32.</p> <p style="text-align: center;">Var. 20<math>\frac{1}{2}</math>°E.</p> <p>Through timber.</p>
1.00	A brook, 4 lks. wide, runs N.W.
40.00	<p>Set a post, 3 ft. long, 3 ins. square, 24 ins. in the ground, for <math>\frac{1}{4}</math> sec. cor., marked EL<math>\frac{1}{4}</math>S on N. face, from which,</p> <p>A fir, 12 ins. diam., bears N.50°W., 15 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p> <p>A fir, 8 ins. diam., bears S. 80°W., 32 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p> <p>The old <math>\frac{1}{4}</math> sec. cor., a badly decayed post, bears W., 19.38 chs. dist. I destroy the post, also the marks on old bearing trees, a fir and pine.</p>
50.50	Top of ridge, course N.W.
78.00	Bottom of canyon, about 600 ft. below ridge, course N.W.
78.50	Dry bed of creek, 25 lks. wide, runs N.W.
80.00	<p>Set a post, 4 ft. long, 4 ins. square, 24 ins. in the ground, for cor. to secs. 31 and 32, marked B L T 1 N R. 37 E on N., S 32 on E. and S 31 on W. faces, with 5 notches on E. and 1 notch on W. faces, from which,</p> <p>A fir, 10 ins. diam., bears N.80°E., 50 lks. dist., marked T 1 N R 37 E S 32 B T.</p>