

Resurvey of Base Line through Range 37 East

Chains	<p>A pine, 10 ins. diam., bears S.5°E., 46 lks. dist., marked T 1 S R 37 E S 6 B T.</p> <p>A fir, 7 ins. diam., bears N.20°W., 72 lks. dist., marked T 1 N R 37 E S 31 B T.</p> <p>The old sec. cor., a post bears W., 22.60 chs. dist. I destroy this post, also the marks on old bearing trees, 3 firs.</p> <p>Land, mountainous.</p> <p>Soil, 3rd rate.</p> <p>Heavily timbered with fir, pine and tamarack.</p> <p>Dense undergrowth of fir, pine and tamarack.</p>
	<p>West on Base Line of S. boundary of sec. 31.</p> <p style="text-align: center;">Var. 20½°E.</p>
	<p>Ascend mountain.</p>
29.00	<p>Top of ridge, about 600 ft. above sec. cor., course S.E.</p>
40.00	<p>Set a basalt stone, 19x10x7 ins., 14 ins. in the ground, for ¼ sec. cor., marked B L ¼ on N. face, from which, A cherry, 3 ins. diam., bears N.30°E., 15 lks. dist., marked ¼ S B T.</p> <p>No other tree within limits.</p> <p>and raised a mound of stone alongside.</p>
	<p>The old ¼ sec. cor., a badly decayed post, bears W. 23.10 chs. dist. I destroy the post and obliterate the marks on old bearing trees.</p>
46.50	<p>Bottom of gulch, about 200 ft. below ridge, course S.E.</p>
103.45	<p>The cor. to Tps. 1 N., Rs. 36 and 37 E., which is a post, 4 ins. square, marked S 31 T 1 N 37 E on N.E., S 36 T 1 N R 36 E on N.W., with 6 notches on N. E. and W. edges, from which,</p> <p>A hemlock, 14 ins. diam., bears N.10°E., 46 lks. dist., marked T 1 N R 37 E S 31 B T.</p> <p>A hemlock, 12 ins. diam., bears N.20°W., 22 lks. dist., marked T 1 N R 36 E S 36 B T.</p> <p>A hemlock, 10 ins. diam., bears S.35°W., 26 lks. dist., marked T 1 S R 36 E S 1 B T.</p>