

Subdivisions of T. 1 N., R. 37 E.

Chains	<p>A fir, 28 ins. diam., bears N.50°W., 66 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>78.50 Top of ridge, about 200 ft. above brook, course N.W.</p> <p>80.00 Set a post 4 ft. long, 4 ins. square, 24 ins. in the ground, for cor. to secs. 27, 28, 33 and 34 marked T 1 N S 27 on N.E., R 37 E S 34 on S.E., S 33 on S.W., S 28 on N.W. faces, with 1 notch on S. and 3 notches on E. edges, from which,</p> <p>A willow, 6 ins. diam., bears N.45°E., 8 lks. dist., marked T 1 N R 37 E S 27 B T.</p> <p>An alder, 4 ins. diam., bears S.70°E., 23 lks. dist., marked T 1 N R 37 E S 34 B T.</p> <p>An alder, 3 ins. diam., bears S.25°W., 14 lks. dist., marked T 1 N R 37 E S 33 B T.</p> <p>An alder, 4 ins. diam., bears N.45°W., 20 lks. dist., marked T 1 N R 37 E S 28 B T.</p> <p>Land, mountainous.</p> <p>Soil, sandy loam, 2nd rate.</p> <p>Heavily timbered with fir, tamarack and pine.</p> <p>Dense undergrowth of fir, tamarack, pine, mountain laurel, alder and willows.</p>
	<p>East on a random line between secs. 27 and 34.</p> <p>Var. 21°E.</p> <p>Descend through timber and brush.</p> <p>40.00 Set temporary $\frac{1}{4}$ sec. cor.</p> <p>52.00 Foot of hill about 1500 ft. below sec. cor., course N.W.</p> <p>54.50 N. fork of Meacham creek, 10 lks. wide, runs N.W.</p> <p>80.54 Intersect 60 lks. N. of the cor. to secs. 26, 27, 34 and 35.</p> <p>Thence I run</p> <p>N.89°34'W. on a true line between secs. 27 and 34.</p> <p>40.27 Set a basalt stone, 16x10x4 ins., 11 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone alongside.</p> <p>80.54 The cor. to secs. 27, 28, 33 and 34.</p>