

Subdivisions of T. 1 N., R. 37 E.

Chains	<p>Land, mountainous. Soil, stony, 3rd rate. Heavily timbered with fir and tamarack. Dense undergrowth of fir, tamarack and mountain laurel.</p>
40.00	<p>North between secs. 27 and 28. Var. 21°E. Descend through timber. Set a basalt stone, 12x9x5 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, from which, A pine, 6 ins. diam., bears S.20°E., 50 lks. dist., marked $\frac{1}{4}$ S B T. A fir, 6 ins. diam., bears S.10°W., 37 lks. dist., marked $\frac{1}{4}$ S B T.</p>
51.50	A spring branch, 3 lks. wide, runs N.E.
61.50	Foot of hill about 1500 ft. below sec. cor., course N.W.
64.50	N. fork of Meacham creek, 10 lks. wide, runs N.W.
66.00	Ascend hill.
80.00	<p>Set a post 4 ft. long, 4 ins. square, 24 ins. in the ground, for cor. to secs. 21, 22, 27 and 28, marked T 1 N S 22 on N.E., R 37 E S 27 on S.E., S 28 on S.W. and S 21 on N.W. faces, with 2 notches on S. and 3 notches on E. edges, from which, A pine, 6 ins. diam., bears N.65°E., 9 lks. dist., marked T 1 N R 37 E S 22 B T. A pine, 4 ins. diam., bears S.60°E., 8 lks. dist., marked T 1 N R 37 E S 27 B T. A pine, 5 ins. diam., bears S.35°W., 15 lks. dist., marked T 1 N R 37 E S 28 B T. A pine, 6 ins. diam., bears N.20°W., 7 lks. dist., marked T 1 N R 37 E S 21 B T.</p>
	<p>Land, mountainous. Soil, stony, 3rd rate. Heavily timbered with fir, tamarack and pine. Dense small growth of pine, fir, tamarack and mountain laurel.</p>
	September 3, 1882.