

## Subdivisions of T. 1 N., R. 37 E.

Chains	<p>Land, mountainous.</p> <p>Soil, 2nd and 3rd rate.</p> <p>Timber, scattering fir, tamarack and pine, with dense undergrowth of buck brush.</p>
	<p>East on a random line between secs. 20 and 29.</p> <p style="text-align: center;">Var. <math>20\frac{1}{4}^{\circ}</math> E.</p>
	<p>Ascend about 100 ft. to</p>
9.00	Top of ridge, course N.
19.00	Bottom of gulch, about 100 ft. below ridge, course N.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
48.00	Top of ridge, about 500 ft. above gulch, course N.
	Descend about 150 ft. to
63.00	A spring branch, 3 lks. wide, runs N.
80.14	Intersect 42 lks. N. of the cor. to secs. 20, 21, 28 and 29.
	Thence I run
	N. $89^{\circ}42'$ W. on a true line between secs. 20 and 29.
40.07	Set a post, 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on N. face, from which,
	<p style="padding-left: 40px;">A fir, 18 ins. diam., bears N. <math>30^{\circ}</math> W., 36 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p>
	<p style="padding-left: 40px;">A fir, 20 ins. diam., bears S. <math>25^{\circ}</math> E., 16 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p>
80.14	The cor. to secs. 19, 20, 29 and 30.
	Land, mountainous.
	Soil, 2nd and 3rd rate.
	Heavily timbered with pine, fir and tamarack.
	Dense undergrowth of pine, fir and buck brush.
	<p>West on a random line between secs. 19 and 30.</p> <p style="text-align: center;">Var. <math>20\frac{1}{4}^{\circ}</math> E.</p>
	Descend through timber.
7.50	Foot of hill, about 200 ft. below cor., course S.W.
10.00	N. fork of Meacham creek, 30 lks. wide, runs S.W.