

Subdivisions of T. 1 N., R. 37 E.

Chains	<p>North between secs. 7 and 8.</p> <p style="text-align: center;">Var. $20\frac{1}{2}^{\circ}$E.</p> <p>Descend through brush and timber.</p> <p>40.00 Set a post, 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on W. face, from which,</p> <p style="padding-left: 40px;">A fir, 4 ins. diam., bears East 33 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p style="padding-left: 40px;">A fir, 5 ins. diam., bears S.5°W., 17 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>48.00 Bottom of canyon about 500 ft. below last sec. cor.</p> <p style="padding-left: 40px;">A brook, 5 lks. wide, runs S.E.</p> <p>Ascend about 600 ft. to</p> <p>78.00 Top of ridge, course S.E.</p> <p>80.00 Set a post, 4 ft. long, 4 ins. square, 24 ins. in the ground, for cor. to secs. 5, 6, 7 and 8 marked T 1 N S 5 on N.E., R 37 E S 8 on S.E., S 7 on S.W., and S 6 on N.W. faces, with 5 notches on S. and E. edges, from which,</p> <p style="padding-left: 40px;">A fir, 8 ins. diam., bears N.10°E., 45 lks. dist., marked T 1 N R 37 E S 5 B T.</p> <p style="padding-left: 40px;">A fir, 14 ins. diam., bears S.45°E., 30 lks. dist., marked T 1 N R 37 E S 8 B T.</p> <p style="padding-left: 40px;">A fir, 12 ins. diam., bears S.10°W., 41 lks. dist., marked T 1 N R 37 E S 7 B T.</p> <p style="padding-left: 40px;">A fir, 20 ins., diam., bears N.40°W., 32 lks. dist., marked T 1 N R 37 E S 6 B T.</p> <p>Land, mountainous.</p> <p>Soil, 2nd rate.</p> <p>Timber, scattering pine, fir and tamarack.</p> <p>Dense undergrowth of pine, fir, tamarack and mountain laurel.</p>
	<p>East on a random line between secs. 5 and 8.</p> <p style="text-align: center;">Var. 19°E.</p>
14.00	Bottom of gulch, about 100 ft. below cor., course S.E.