

Subdivisions of T. 1 N., R. 37 E.

Chains

An alder, 4 ins. diam., bears S.30°E., 20 lks. dist.,
marked $\frac{1}{4}$ S B T.

An alder, 4 ins. diam., bears S.40°W., 11 lks. dist.,
marked $\frac{1}{4}$ S B T.

80.76 The cor. to secs. 5, 6, 7 and 8.

Land, mountainous.

Soil, 2nd rate.

Heavily timbered with pine, fir and tamarack.

Dense undergrowth of pine, fir, tamarack and alder.

September 10, 1882.

General Description

The land in this township is entirely rough and mountainous. The soil is mostly third rate, but there is some fair second rate. There is an abundance of bunch grass over most of the hills and it is splendid for grazing purposes. The entire township is covered with pine, fir and tamarack timber, mostly scattering but quite dense in places. The timber is of good quality, but is too scarce and secluded to be of much value.

I found no settler in this township.

(Signed) Herman D. Gradon
U.S. Dept. Surveyor.

Resurvey of the Exterior Boundaries of T.2N., R.37 E.
Surveyed by Charles L. Campbell, joint contract No. 733.
Dated March 22, 1901.

(South Boundary)

Since T. 1 N., R. 37 E. has been subdivided, I resurvey the line between Tps. 1 and 2 N., R. 37 E. as follows:
I reestablish all old obliterated cors. in their original position.

July 11: at 7 h 50 m a.m., l.m.t., I set off 45°36' on the lat. arc., 22° 11' N. on the decl. arc., and determine a true meridian with the solar at the cor. of Tps. 1 and 2 N., Rs. 37 and 38 E., described heretofore.