

## Resurvey of South Bdy. of T. 2 N., R. 37 E.

Chains	S.89°37'W. on old township line between secs. 3 and 34. Over level ground on summit of divide between Meacham Creek and Umatilla River, bears N.30°W., S.30°E.
3.00	Black Mt. pack trail, bears N.60°W., S.80°E. Descend steep S. slope through scattering timber and undergrowth.
36.25	Foot of hill, 450 below summit, bears N. and S. Creek, 3 lks. wide, course S.30°E.---headwaters of N. fork, Meacham Creek. Ascend.
40.41	Intersect old $\frac{1}{4}$ sec. cor., which is a post greatly decayed, marks obliterated and witnessed as described by the surveyor general. I destroy old post and set new post, 3 ft. long, 3 ins. sq., 24 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S 34 on N. face, and S 3 on S. face, from which the witness trees bear as stated by the surveyor general. S.89°54'W. Ascend steep E. slope of mountain.
79.10	Leave timber, and undergrowth, bears N. and S., and pass over level, rocky plateau.
80.98	Intersect old cor. of secs. 3, 4, 33 and 34, which is a decayed post in mound of stone, marks all obliterated. I set new post, 3 ft. long, 6 ins. sq., at the same point, 24 ins. in the ground, for cor. of secs. 3, 4, 33 and 34, marked T. 2 N S 34 on N.E., R 37 E S 3 on S.E., T 1 N S 4 on S.W., and S.33 on N.W. faces, with 3 notches on E. and W. edges. Rebuild the stone mound N. of the cor. Land, mountainous. Soil, stony, 3rd and 4th rate. Timber, fir, pine, spruce and larch. Undergrowth, mountain laurel, small firs, huckleberry and yew. Mountainous land, 80.98 chs.
July 11, 1901.	