

## Resurvey of South Edy. of T. 2 N., R. 37 E.

Chains 75.00	Spring branch, 3 lks. wide, course N. Steeper ascent.
82.00	Leave dense thickets and fir timber, bears N. and S.
84.00	Top of rise, 100 ft. above creek, bears N. W. and S.
84.75	Buck Mt. pack trail, bears N.80°W., S.80°E. Descend gradually over plateau through scattering timber.
97.25	Leave plateau, bears N.W., S.E. and descend along S. slope through scattering timber and dense undergrowth.
100.15	Intersect the cor. of Tps. 1 and 2 N., Rs. 36 and 37 E., which is a post almost rotted away, marks obliterated, and witnessed as described by the surveyor general, with the exception of the NE. bearingtree, which bears N.32° E., 18 lks. dist., instead of N.71°E., 91 lks., as described by the surveyor general. I set basalt stone, 24x20x8 ins., 18 ins. in the ground, at the same point, for cor. of Tps. 1 and 2 N., Rs. 36 and 37 E., marked with 6 notches on each edge. Land, rolling and mountainous. Soil, loam, 1st and 2nd rates. Timber, pine, fir and tamarack. Undergrowth, alder, small firs, huckleberry and vine maple. Mountainous or heavily timbered land, 90.00 chs. Overcast at noon prevented taking the latitude.
	June 11, 1901.