

West Bdy. of Tp. 1 S., R.31 E., W.M.
 As surveyed by David P. Thompson, Deputy Surveyor
 Under Contract No. 106 and
 Dated Aug. 16, 1864.

Chains		Feet
	I commence at the Base Line at the established Cor. to T.1 S., Rs.30 & 31 E. , and run S. on W. Bdy. of Sec. 6.	
	Var. 15° 45' E.	
40.00	Set a stone, 15 x 8 x 8 for $\frac{1}{4}$ Secs. Cor.	
42.00	Road brs. E. & W.	
80.00	Set a stone, 18 x 12 x 6 in. for Cor. to Secs. 6, 7, 1 & 12.	
	Land; rolling.	
	Soil; 2nd rate.	
<hr/>		
	S. on W. Bdy. of Sec. 7.	
	Var. 19° 30' E.	
40.00	Set a stone, 18 x 15 x 5 ins. for $\frac{1}{4}$ Sec. Cor. in ravine which brs. N.E.	
58.80	Dailys Road brs. E.& W.	
80;00	Set a stone, 17 x 12 x 10 ins. for Cor. to Secs. 12, 13, 7 & 18.	
	Land; rolling.	
	Soil; 2nd rate.	
<hr/>		
	S. on W. Bdy. of Sec. 18.	
	Var. 20° 45' E.	
40.00	Set a stone, 15 x 10 x 8 ins. for $\frac{1}{4}$ Secs. Cor.	
80.00	Set a post for Cor. to Secs. 18, 19, 13 & 24, in mound of earth with charred stake, pits, trench etc., as per instructions.	
	Land; rolling.	
	Soil; 2nd rate.	
<hr/>		
	S. on W. Bdy. to Sec. 19.	
	Var. 19° E.	
40.00	Set a stone, 18 x 10 x 5 ins. for $\frac{1}{4}$ Sec. Cor.	
80.00	Set a post for Cor. to Secs. 24, 25, 19 & 30, in mound of earth with charred stake, pits and trench, etc., as per instructions.	
	Land; gently rolling. Soil; 2nd rate.	