

Subdivisional lines T.1 S., R.30 $\frac{1}{2}$ E., W.M.

Chains		Feet
	East on a random line bet. Secs. 25 & 36. Var. 22° 00' E.	
36.00	Wagon Road, course N.&S.; from settlements to timber in the mountains.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
78.00	A ravine, course N., about 80 ft. deep.	
79.88	Intersected E. Bdy., 28 lks. N. of stone (18 x 12 x 8 on W. face of slope), Cor. to Secs. 25 & 36. Stone partly in ground and partly supported by stones laid alongside, marked with 5 notches on the N. and blank on the S., as it should be.	40
	Thence I run N. 89° 48' W. on a true line bet. Secs. 25 & 36. Var. 25° 00' E.	
39.94	Set basalt stone, 17 x 7 x 6 ins., 12 ins. in ground, on level, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Dug pits 18 x 18 x 12 ins. E. & W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth, 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base, alongside.	
79.88	The Cor. to Secs. 25, 26, 35 & 36. Land; Surface nearly level, except ravine on E. $\frac{1}{2}$ mile. Soil; 2nd & 3rd rate, stony in a few places. Good grass. The larger part good farming land.	
	W. on a random line bet. Secs. 26 & 35. Var. 22° 00' E.	
9.88	Intersected W. Bdy. 7 lks. S. of Cor. to Secs. 25 & 36, a stone, projecting about 10 ins. above ground and marked with 5 notches on N. edge and blank on S., standing just S. of ravine about 40 ft. below the starting Cor.	
	Thence I run S. 89° 33' E. on a true line bet. Secs. 26 & 35. Var. 22° 20' E.	
9.88	The Cor. to Secs. 25, 26, 35 & 36. Land; surface rolling Soil; 3rd rate & stony.	