

Subdivisional lines T. 1 S., R. 30 $\frac{1}{2}$  E., W.M.

Chains		Feet
9.80	Intersected W. Bdy. 21 lks. N. of Cor. to Secs. 12 & 13, which is a basalt stone, projecting about 7 ins. above ground, marked with 2 notches on N. edge.	
	I run thence N.88° 47' E. on a true line bet. Secs. 11 & 14. Var. 22° 00' E.	
9.80	The Cor. to Secs. 11, 12, 13 & 14. Land; surface rolling. Soil; 2nd rate.	
	N. bet. Secs. 11 & 12. Slightly ascending. Var. 22° 30' E.	
40.00	Set a basalt stone, 24 x 10 x 5 ins., 18 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Dug pits, 18 x 18 x 12 ins., N. & S. of stone, 5 $\frac{1}{2}$ ft. dist. and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base alongside. Slightly descending.	
41.25	Wagon Road, course N.E. & S.W. from settlement to timber.	
80.00	Set a basalt stone, 14 x 8 x 6 ins., 9 ins. in ground for Cor. to Secs. 1, 2, 11 & 12, marked with 5 notches on S. and 1 notch on E. edges. Drove a stake, marked T 1 S, S 1 on N.E. R 30 $\frac{1}{2}$ E, S 12 on S.E. S 11 on S.W. and S 2 on N.W. and raised a mound of stone around stake alongside stone in lieu of pits. Land; surface slightly undulating. Soil; good 2nd rate.	
	E. on a random line bet. Secs. 1 & 12. Var. 21° 15' E.	
17.50	Plowed land on N. of line.	
30.00	Leave plowed land. Thomas Thrasher's house brs. N.33° E.	
40.00	Thomas Thrasher's house brs. N.2° E. Set temp. $\frac{1}{4}$ Sec. Cor.	