

T. 1 S., R. 31 E., W.M.

Chains	earth, with charred stake, pits, trench, etc., as per instructions.	Feet +600
	Land; steep hills. Soil; 2nd rate.	
	E. on N. Bdy. of Sec. 2. Var. 17° 30' E.	
	Ascend hill.	
40.00	Set stone, 18 x 15 x 6 ins. for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 20 x 8 x 6 ins. for Cor. to Secs. 1, 2, 35 & 36.	+100
	Land; gently rolling. Soil; good 2nd rate.	
	E. on N. Bdy. Sec. 1 Var. 23° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth with charred stake, pits, trench, etc. as per instructions.	
42.50	Road brs. N.W. & S.E.	
75.75	Spring flows N.W.	
80.00	The Cor. to Tps. 1 & 2 S., Rs. 32 & 33 E.	+600
	Land; hilly. Soil: 2nd rate.	
	Oct. 11, 1864.	
	Subdivisional lines of T. 1 S., R. 31 E., W.M. As surveyed by Samuel Chaplin, Deputy Surveyor. Under Contract No. 107. Dated Sept. 21, 1864.	
	N. bet. Secs. 35 & 36.	
1.500	Creek, 5 lks. wide, runs N.E.	
15.00	Ascend hill.	
40.00	Set stone, 16 x 12 x 8 for $\frac{1}{4}$ Sec. Cor.	
70.00	Top of hill, brs. N.E. & S.W.	
80.00	Set post for Cor. to Secs. 25, 26, 35 & 36, in mound of earth with charred stake, pits, trench, etc. as per instructions.	