

T. 1 S., R. 31 E., W.M.

Chains		Feet
	N. bet. Secs. 34 & 35.	
40.00	Set post for $\frac{1}{4}$ Secs. Cor. in mound of earth with charred stake, pits, etc. as per instructions.	
80.00	Set post for Cor. to Secs. 34, 35, 26 & 27 in mound of earth with charred stake, pits, etc. as per instructions. Land; level. Soil; 1st rate.	
40.00	E. on a random line bet. Secs. 26 & 35.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.12	Intersect, 27 lks. S. of Cor. to Secs. 25, 26, 35 & 36, from which Cor., I run S. 89° 48' W. on a true line bet. Secs. 26 & 35.	
40.06	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth with charred stake, pits, etc., as per instructions.	
80.12	The Cor. to Secs. 34, 35, 26 & 27. Land; gently rolling. Soil; good 2nd rate.	
	N. bet. Secs. 26 & 27. Descend hill. Var. 12 $\frac{1}{2}$ ° E.	
21.50	Ravine brs. N.E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth with charred stake, pits, etc. as per instructions.	-300
72.50	Foot of hill, ravine brs. E. Ascend	
80.00	Set stone, 22 x 8 x 6 for Cor. to Secs. 22, 23, 26 & 27.. Land; hilly. Soil; 2nd rate.	
	E. on a random line bet. Secs. 23 & 26.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.40	Intersect N. & S. line, 33 lks. S. of Cor. to Secs. 23, 24, 25 & 26, from which Cor. I run S. 89° 46' W. on a true line bet. Secs. 23 & 26. Ascend hill.	