

Northor Bdy. of Tp. 2 S., R. 32 E., W.M.
 As surveyed by David P. Thompson, Deputy Surveyor.
 Under Contract No. 106.
 Dated Aug. 16, 1864.

Chains		Feet
	<p>I now run a random line W. bet. Tps. 1 & 2 S. and set temp. half mile and mile posts at 40.00 and 80.00 chains</p> <p>Find the Tp; line to be 6 miles and the intersection at the Tp. Cor.</p> <p>From the Cor. to Tps. 1 & 2 S., Rs. 31 & 32 E., I run E. on a true line.</p> <p style="text-align: right;">Oct. 10, 1864.</p>	
	<p>E. on N. Bdy. of Sec. 6.</p> <p style="text-align: right;">Var. 20° 30' E.</p>	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth, with charred stake, pits, trench, etc., as per instructions.	
80.00	Set post for Cor. to Secs. 5, 6, 31 & 32, in mound of earth with charred stake, pits, trench, etc. as per instructions.	
	<p>Land; level.</p> <p>Soil; good 2nd rate.</p>	
	<p>E. on N. Bdy. of Sec. 5</p> <p style="text-align: right;">Var. 19$\frac{1}{2}$° E.</p>	
	Descend hill.	
12.50	Brook, 2 lks. wide, runs N.E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, trench, etc., as per instructions.	
54.50	Ravine brs. N.	
80.00	Set stone, 28 x 10 x 6 ins. for Cor. to Secs. 4, 5, 32 & 33.	-300
	<p>Land; rolling.</p> <p>Soil; 2nd rate.</p>	
	<p>E. on N. Bdy. of Sec. 4.</p> <p style="text-align: right;">Var. 18° 45' E.</p>	
	Descend hill.	
40.00	Set stone, 20 x 15 x 10 ins. for $\frac{1}{4}$ Sec. Cor.	-300
45.00	Foot of hill	
50.75	E. Fork of Birch Creek, 10 lks. wide, runs N.W.	
53.00	Road brs. N.W. & S.E.	