

Subdivisional lines, T. 1 S., R. 32 E., W.M.

Chains		Feet
	N. bet. Secs. 13 & 14. Var. $17\frac{1}{2}^{\circ}$ E. Descend hill.	
40.00	Set stone, 12 x 12 x 5 for $\frac{1}{4}$ Sec, Cor.	
80.00	Set post for Cor. to Secs. 11, 12, 13 & 14, in mound of earth with pits, charred stake, etc., as per instructions.	
	Land; rolling. Soil; 2nd rate.	
	E. on a random line bet. Secs. 12 & 13.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.25	Intersect E. Bdy., 74 lks. N. of Cor. to Secs. 12 & 13, from which, I run N. $89^{\circ} 28'$ W. on a true line bet. Secs. 12 & 13. Descend hill.	
11.80	Ravine brs. N.W.	
40.12	Set post for $\frac{1}{4}$ Sec. Cor. , in mound of earth, with charred stake, pits, etc., as per instructions.	
80.25	The Cor. to Secs. 11, 12, 13 & 14.	300
	Land; hilly Soil; 2nd rate, Fine grass.	
	N. bet. Secs. 11 & 12. Var. $21\frac{1}{2}^{\circ}$ E. Descend hill.	
13.00	Spring, 100 lks. W. of line.	
40.00	Set stone, 18 x 12 x 12, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post for Cor. to Secs. 1, 2, 11 & 12, in mound of earth with charred stake, pits, etc., as per instructions.	
	Land; gently rolling. Soil; 1st rate.	
	E. on a random line bet. Secs. 1 & 12.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	