

Subdivisional lines, T. 1 S., R. 32 E., W.M.

| Chains | | Feet |
|--------|---|------|
| | E. on a random line bet. Secs. 15 & 22. | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. | |
| 79.64 | Intersect N. & S. line at Cor. to Secs. 14, 15, 22 & 23, from which, I run W. on a true line bet. Secs. 15 & 22. | |
| 17.00 | Dry bed of creek, course N.W. | |
| 27.00 | Road brs. N.W. & S.E. | |
| 36.25 | Road brs. N.W. & S.E. | |
| 39.82 | Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions. | |
| 79.64 | The Cor. to Secs. 21, 22, 15 & 16. Land; level. Soil; 1st rate. | |
| | N. bet. Secs. 15 & 16. Var. $19\frac{3}{4}^{\circ}$ E. | |
| 40.00 | Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions. | |
| 80.00 | Set post for Cor. to Secs. 9, 10, 15 & 16, in mound of earth, with charred steke, pits, trench, etc., as per instructions. Land; level. Soil; 1st rate. | |
| ✓ | E. on a random line bet. Secs. 10 & 15. | |
| 40.00 | Set post for temp. $\frac{1}{4}$ Sec. Cor. | |
| 79.50 | Intersect N. & S. line at Cor. to Secs. 10, 11, 14 & 15, from which, I run W. on a true line bet. Secs. 10 & 15. | |
| 6.00 | Road brs. N.W. & S.E. | |
| 17.00 | Ravine brs. N.W. & S.E. | |
| 39.75 | Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions. | |
| 43.00 | Road brs. N.W. & S.E. | |
| 79.50 | The Cor. to Secs. 19, 10, 15 & 16. Land; level. Soil; 1st rate. | |