

Subdivisional lines, T. 1 S., R. 32 E., W.M.

Chains		Feet
80.66	Intersect N. & S. line at Cor. to Secs. 21, 22, 27 & 28, from which, I run W. on a true line bet. Secs. 21 & 28	
40.33	Set stone, 18 x 18 x 6 for $\frac{1}{4}$ Sec. Cor.	
47.25	Descend bluff, 200 ft. high, brs. N. & S.	
58.50	E. fork of Birch Creek, dry bed, course N.	
69.50	Road brs. N. & S.	
80.66	The Cor. to Secs. 20, 21, 28 & 29. Land; rolling. Soil; 1st rate. Some cottonwood timber on bank of creek. Oct. 17, 1864.	
	N. bet. Secs. 20 & 21 Var. $19\frac{1}{2}^{\circ}$ E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth, with charred stake, pits, etc., as per instructions.	
79.00	Road brs. N.W. & S.E.	
80.00	Set post for Cor. to Secs. 16, 17, 20 & 21, in mound, with charred stake, pits, etc., as per instructions. Land; level. Soil; 1st rate.	
	E. on a random line bet. Secs. 16 & 21.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.70	Intersect N. & S. line, 30 lks. N. of Cor. to Secs. 15, 16 21 & 22, from which, I run N. $89^{\circ} 47'$ W. on a true line bet. Secs. 16 & 21.	
32.00	Road brs. N. & S.	
40.35	Set stone, 15 x 12 x 5 for $\frac{1}{4}$ Sec. Cor.	
65.00	Enter field brs. N. & S.	
72.50	E. fork of Birch Creek, 8 lks. wide, runs. N.W.	
80.70	The Cor. to Secs. 16, 17, 20 & 21. Land; rolling. Soil; 1st rate.	