

Subdivisional lines, T.1 S., R. 32 E., W.M.

Chains	Feet
	E. on a random line bet. Secs. 4 & 9.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.25	Intersect N. & S. line at Cor. to Secs. 3, 4, 9 & 10, from which Cor., I run
	W. on a true line bet. Secs. 4 & 9.
38.25	Road brs. N. & S.
40.02	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stakes, pits, etc., as per instructions.
53.00	Birch Creek, 10 lks. wide, runs N.E.
80.25	The Cor. to Secs. 4, 5, 8 & 9. Land; rolling. Soil; 1st rate.
	N. on a random line bet. Secs. 4 & 5. Var. $18\frac{1}{2}^{\circ}$ E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.85	Intersect N. Bdy. at Cor. to Secs. 4 & 5, from which, I run
	S. on a true line bet. Secs. 4 & 5.
39.85	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.
79.85	The Cor. to Secs. 4, 5, 8 & 9. Land; gently rolling. Soil; 1st rate.
	N. bet. Secs. 31 & 32.
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.
80.00	Set stone, 17 x 11 x 5 for Cor. to Secs. 29, 30, 31 & 32. Land; gently rolling. Soil; good 2nd rate.
	E. on a random line bet. Secs. 29 & 32.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.80	Intersect N. & S. line at Cor to Secs. 28, 29, 32 & 33, from which Cor., I run