

Subdivisional lines T. 1 S., R. 32 E., W.M.

Chains		Feet
	W. on a random line bet. Secs. 19 & 30.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.30	Intersect W. Bdy. at Cor. to Secs. 19 & 30, from which, I run East on a true line bet. Secs. 19 & 30.	
11.00	Enter field, brs. N.E. & S.W.	
19.00	Foot of hill.	
22.00	Birch Creek, 10 lks. wide, runs N.E. Gilliland's house brs. N.10°E., 15 chs. dist.	
31.75	Leave field, brs. N.E. & S.W.	
40.30	Set stone, 20 x 10 x 10 for $\frac{1}{4}$ Sec. Cor.	
80.30	The Cor. to Secs. 19, 20, 29 & 30. Land; rolling. Soil; 1st rate.	
	N. bet. Secs. 19 & 20.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
68.65	Road brs. N.E. & S.W.	
71.03	Enter field, brs. N.E. & S.W.	
80.00	Set post for Cor. to Secs. 17, 18, 19 and 20., in mound of earth, with charred stake, pits, etc., as per instruct- ions. Land; gently rolling. Soil: 1st rate.	
	E. on a random line, bet. Secs. 17 & 20.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.31	Intersect N. & S. line, 21 lks. S. of Cor. to Secs. 16, 17, 20 & 21, from which, I run S. 89° 51' W. on a true line bet. Secs. 17 & 20.	
39.65	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
66.21	Enter field, brs. N.E. & S.W.	
79.31	The Cor. to Secs. 17, 18, 19 & 20. Land; gently rolling. Soil; 1st rate.	