

Subdivisional lines, T. 1 S., R. 32 E., W.M.

Chains		Feet
	W. on a random line bet: Secs. 18 & 19.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect W. Bdy. at Cor. to Secs. 18 & 19, from which, I run	
	E. on a true line bet. Sec.s 18 & 19.	
15.00	Descend hill.	
40.00	Set stone, 20 x 12 x 10, for $\frac{1}{4}$ Sec/ Cor.	
66.00	Foot of hill.	400
69.40	Birch Creek, 8 lks. wide runs N.E.	
72.63	Enter field, brs. N.E. & S.W.	
80.00	The Cor. to Secs. 17, 18, 19 & 20. Land; hilly. Soil; 2nd rate.	
N. bet. Secs. 17 & 18.		
	Var. 20° E.	
9.00	Leave field.	
9.25	Birch Creek, 8 lks. wide, runs N.E.	
18.00	Ben Smith's, House brs. E., 20 chs. dist.	
30.90	Road brs. E. & W.	
40.00	Set stone, 18 x 6 x 6 for $\frac{1}{4}$ Sec. Cor.	
55.00	Top of hill	4300
80.00	Set stone, 18 x 10 x 10 for Cor. to Secs. 7, 8, 17 & 18. Land; hilly. Soil; 1st rate.	
E. on a random line bet. Secs. 8 & 17.		
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.25	Intersect N. & S. line at Cor. to Secs. 8, 9, 16 & 17, from which, I run	
	W. on a true line bet. Secs. 8 & 17.	
39.62	Set stone, 22 x 8 x 4 for $\frac{1}{4}$ Sec. Cor.	
79.25	The Cor. to Secs. 7, 8, 17 & 18. Land; gently rolling. Soil; 1st rate.	