

T. 1 S., R. 33 E., W.M.

| Chains | | Feet |
|--------|---|------|
| | W. on a true line bet. Secs. 3 & 34. Var. 20° E. | |
| 11.50 | Summit | +500 |
| 31.00 | Gulch, course S. | -100 |
| 35.00 | Ridge | +200 |
| 40.00 | Set a basalt stone, 14 x 10 x 8 ins., 9 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised a mound of stone alongside. Pits impracticable. | |
| 62.00 | Gulch, course S.E. | -150 |
| 80.00 | Set a basalt stone, 20 x 14 x 6 ins., 15 ins. in ground for Cor. to Secs. 3, 4, 34 & 33. Marked 3 notches on E. & W. edges, raised mound of stone alongside. Pits impracticable. | |
| | Land; mountainous, 80.00 chs. No timber. Good bunch grass. Soil; 3rd rate. | |
| | W. on a true line bet. Secs. 4 & 33. Var. 19° 15' E. | |
| 19.55 | Head of canyon, course N. Enter timber. | -200 |
| 25.50 | Summit of point. | +100 |
| 40.00 | Set a basalt stone, 16 x 10 x 8 ins., 11 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which, A tamarack, 16 ins. diam., brs. S.45° E., dist. 25 lks. marked $\frac{1}{4}$ S., B.T. | |
| | No other tree in limits, raised mound of stone alongside. Leave timber. Ascend. | |
| 80.00 | Set basalt stone, 16 x 12 x 10 ins., 11 ins. in ground for Cor. to Secs. 4, 5, 32 & 33. Marked with 4 notches on E. and 2 notches on W. edges. Raised mound of stone alongside. Pits impracticable. | +200 |
| | Land; mountainous, 25.50 chs. Table land, 54.50 chs. Timber; 20.45 chs. Soil; rocky, 4th rate. | |