

Subdivisional Lines, T. 1 S., R. 33 E., W.M.

Chains		Feet
	E. on a random bet. Secs. 25 & 36. Var. 20° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect Tp. line, 10 lks. S. of Cor: to Secs. 30,31,25 and 36. Thence I run S.89° 56' W. on a true line bet. Secs. 25 & 36.	
40.00	Set a basalt stone, 16 x 12 x 10 ins., 10 ins. in ground, marked $\frac{1}{4}$ on N. face for $\frac{1}{4}$ Sec. Cor. Raised a mound of stone around it. Pits impracticable.	
80.00	To Cor. to Secs. 25, 26, 35 & 36. Land; rolling, scattering bunch grass. Soil; 4th rate.	-200
	N. bet. Secs. 25 & 26. Var. 20° E.	
5.00	Summit of Ridge, course N.E.	
40.00	Set a basalt stone, 16 x 12 x 10 ins. , 12 ins. in ground marked $\frac{1}{4}$ on W. face for $\frac{1}{4}$ Sec. Cor., from which, A pine, 20 ins. diam., brs. N.60° E., 57 lks. dist., marked $\frac{1}{4}$ S., B.T. Also, A pine, 15 ins. diam., brs. N.45° W., 20 lks. dist., marked $\frac{1}{4}$ S., B.T.	
43.50	Branch of McKay Creek, course E.	-250
80.00	Set a basalt stone, 12 x 10 x 6 ins., 8 ins. in ground, marked 2 notches on S. edge and 1 notch on E. edge, for Cor. to Secs. 23, 24, 25 & 26. Raised a mound of stone around it. Pits impracticable. Land; mountainous and broken, 80 chs. Good timber on N. side of line. Soil; 2nd rate.	
	E. on random line bet. Secs. 24 & 25. Var. 16° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect Tp. line, 30 lks. N. of Cor. to Secs..24, 25, 19 and 30. Thence I run	