

Subdivisional Lines, T. 1 S., R. 33 E., W.M.

| Chains  |  | Feet |
|---|--|------|
| 40.00   | Set temp. $\frac{1}{4}$ Sec. Cor.  |      |
| 80.07   | Intersect Tp. line, 30 lks. N. of Cot. to Secs. 18, 19, 13 and 24. Thence I run, N.89° 47' W. on a true line.  |      |
| 24.00   | Canyon, course N.E.<br>Ascend  | -200 |
| 40.03   | Set a basalt stone, 16 x 12 x 10 ins., 11 ins. in ground, marked $\frac{1}{4}$ on N, face for $\frac{1}{4}$ Sec. Cor. Raised mound of stone around it. Pits impracticable.   |      |
| 60.00   | Top of mountain.<br>Descend.   | +800 |
| 80.07   | To Cor. to Secs. 13, 14, 23 & 24.<br>Land; rough and mountainous, 80.07 chs.<br>Poor bunch grass.<br>Soil; 4th rate.   |      |
| N. bet. Secs. 13 & 14.<br>Var. 21° E.           |  |      |
| 7.50  | Gulch, course N.W.   | -400 |
| 20.50   | Top of Ridge   | +200 |
| 28.50   | Gulch, course N.W.   | -150 |
| 34.00   | Top of Ridge   | +400 |
| 40.00   | Set basalt stone, 24 x 24 x 12 ins., 18 ins. ground, marked $\frac{1}{4}$ on W. face for $\frac{1}{4}$ Sec. Cor. Raised mound of stone around it. Pits impracticable.  |      |
| 45.00   | Gulch, course W.   | -160 |
| 50.00   | Top of hill  | +600 |
| 80.00   | Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground, for Cor. to Secs. 11, 12, 13 & 14, marked with 4 notches on S. edge and 1 notch on E. edge. Raised mound of stone around it. Pits impracticable.<br>Land; mountainous, 80 chs.<br>Soil; 3rd rate. Bunchgrass. |      |
| E. on random bet. Secs. 12 & 13.<br>Var. 19° E. |  |      |