

## Subdivisional Lines, T. 1 S., R. 33 E., W.M.

Chains		Feet
	N. bet. Secs. 22 & 23. Var. 19° E.	
40.00	Set basalt stone, 14 x 10 x 10 ins., 9 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised a mound of stone around it. Pits impracticable.	+400
63.00	Summit and trail, course N.E.	+100
80.00	Set basalt stone, 20 x 16 x 5 ins., 15 ins. in ground, for Cor. to Secs. 14, 15, 22 & 23, marked 2 notches on E. edge and 3 notches on S. edge. Raised a mound of stone around it. Pits impracticable.	-150
	Land; mountainous, 80 chs. Bunch grass. Soil; 2nd rate.	
	E. on a random bet. Secs. 14 and 23. Var. 21° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.16	Intersect N. & S. line, 72 lks. S. of Cor. to Secs. 13, 14, 23 & 24. Thence I run S. 89° 29' W. on a true line	
8.00	Summit	+150
20.75	Gulch	-200
40.08	Set basalt stone, 14 x 12 x 10 ins., 9 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. Face. Raised mound of stone around it. Pits impracticable.	
52.00	Summit trail, course E. & W.	+200
72.00	Summit, course N.	+ 70
80.16	To Cor. to Secs. 14, 15, 22 & 23. Land; mountainous and rocky, 80.16 chs. Good bunchgrass. Soil; 3rd rate.	
	N. bet. Secs. 14 & 15. Var. 21° E.	
	Descend.	
17.75	Dry branch in canyon, course N.E. Ascend.	-400