

Subdivisional Lines, T. 1 S., R. 33 E., W.M.

Chains		Feet
	<p>$\frac{1}{4}$ S., B.T.</p> <p>A pine, 4 ins. diam., brs. S., 12 lks. dist., marked</p> <p>$\frac{1}{4}$ S., B.T.</p>	
61.50	Canyon, course N. 80° E.	
79.75	To Cor. to Secs. 27, 28, 33 & 34.	
	Land; mountainous, 79.75 chs. Covered with pine timber, poor quality.	
	Soil; 3rd rate.	
	July 13, 1887.	
	N. bet. Secs., 27 & 28.	
	Var. 20° 15' E.	
30.45	Trail, course E. & W.	+200
32.00	Summit, " "	+ 20
40.00	Set a basalt stone, 18 x 16 x 16 ins., 13 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone around it. Pits impracticable.	
74.40	Canyon, course E.	-400
80.00	Set a basalt stone, 18 x 12 x 6 ins., 13 ins. in ground, for Cor. to Secs. 21, 22, 27 & 28, marked, 2 notches on S. and 3 notches on E. edges. Raised mound of stone around it. Pits impracticable.	
	Land; mountainous, 80.00 chs.	
	Soil; 3rd rate.	
	Good bunch grass.	
	E. on random bet. Secs. 22 & 27.	
	Var. 15° 45' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.86	Intersect N. & S. line at Cor. to Secs. 22, 23, 26 & 27. Thence I run	
	W. on a true line	
39.93	Set basalt stone, 14 x 10 x 6 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone around it. Pits impracticable.	
64.75	Canyon	- 20