

Subdivisional Lines, T. 1 S., R. 33 E., W.M.

Chains		Feet
72.00	Leave bottom	
79.86	To Cor. to Secs. 21, 22, 27 & 28. Land; mountainous, 79.86 chs. Line running up N. side of canyon. Soil; 3rd rate. Scattering pine timber. July, 14, 1887.	
N. bet. Secs. 21 & 22. Var. 15° 45' E.		
8.00	Summit, course E.	+150
35.50	Canyon " N.E.	-150
40.00	Set basalt stone, 24 x 16 x 8 ins., 18 ins in ground in edge of rimrock for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone around it. Pits impracticable.	
50.00	Table land.	
63.50	Trail, course E. & W.	
72.50	Leave tableland.	
80.00	Set basalt stone, 18 x 12 x 12 ins., 13 ins. in ground for Cor. to Secs. 15, 16, 21 & 22, marked, 3 notches on S. & E. edges. Raised mound of stone around it. Pits impracticable. Land; mountainous, 57.50 chs. Soil; 2nd rate. Good bunch grass.	
E. on random bet. Secs. 15 & 22. Var. 21° 15' E.		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect N. & S. line, 63 lks. S. of Cor. to Secs. 14, 15, 22 & 23. Thence I run S.89° 33' W. on a true line	
10.00	Canyon, course N.	-100
15.00	Summit table land	+200