

Subdivisional Lines, T. 1 S., R. 33 E., W.M.

Chains		Feet
	<p>4½ ft. base alongside.</p> <p>Land; mountainous 80 chs.</p> <p>Soil; 2nd rate.</p> <p>Good bunch grass.</p>	
	<p>E. on random bet. Secs. 4 & 9.</p> <p style="text-align: right;">Var. 18° 45' E.</p>	
40.00	Set temp. ¼ Sec. Cor.	
79.80	Intersect N. & S. Line at Cor. to Secs. 3, 4, 9 & 10. Thence I run W. on a true line.	
25.00	Gulch, course N.	- 50
39.90	Set basalt stone, 10 x 8 x 8 ins., 6 ins. in ground, for ¼ Sec. Cor., marked ¼ on N. face. Raised mound of stone around it. Pits impracticable.	
40.00	Top of ridge, course N.	+100
44.00	Gulch " "	-100
65.00	Top of ridge	+400
79.80	To Cor. to Secs. 4, 5, 8 & 9. Land; mountainous, 54.80 chs. Soil; 2nd rate. Bunch grass.	
	<p>N. on a true line bet. Secs. 4 & 5.</p> <p style="text-align: right;">Var. 18° 45' E.</p>	
22.50	Creek bottom	-150
32.25	Wagon Road	
35.00	McKay Creek, 20 lks. wide, course W.	
40.00	Set a post, 36 x 3 x 3 ins., 24 ins. in ground, for ¼ Sec. Cor., marked ¼ S. on W. face, from which, A balm, 6 ins. diam., brs. S.75° E., 65 lks. dist., marked ¼ S., B.T. A balm, 6 ins. diam., brs. S.65° W., 85 lks. dist., marked ¼ S., B.T.	
	Leave bottom.	
50.00	Summit of ridge	+100
55.50	Gulch, course S.W.	- 20
67.50	Ridge, course W.	+100