

Subdivisional Lines, T. 1 S., R. 33 E., W.M.

Chains		Feet
	<p>C.C., 5 notches on S. and 1 notch on N. edges. Dug pits 18' x 18 x 12 ins., N. & S. & E. of stone, 5½ ft. dist., raised mound of earth, 2 ft. high, 4½ ft. base alongside.</p> <p>Land; rolling.</p> <p>Soil; 2nd rate. Poor bunch grass.</p>	
	<p>N. on true line bet. Secs. 5 & 6.</p> <p style="text-align: center;">Var. 13° E.</p>	
11.00	Summit of ridge, course N.W.	+400
32.85	Fence, course E. & W.	-300
40.00	<p>Set basalt stone, 12 x 10 x 10 ins., 8 ins. in ground for ¼ Sec. Cor., marked ¼ on W. face, dug pits, 18 x 18 x 12 ins. N. & S. of Cor., 5½ ft. dist. raised earth mound 1½ ft. high, 3½ ft. base alongside.</p>	
57.70	McKay Creek, water in holes, course W.	
86.57	<p>Intersect Tp. line, 400 lks. W. of ¼ Sec. Cor. on S. Bdy. Sec. 32, set basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for Closing Cor. to Secs. 5 & 6, marked C.C. 5 notches on E. and 1 notch on W. Dug pits, 18 x 18 x 12 ins. S., E., & W. of stone, 5½ ft. dist., Raised earth mound 2 ft. high, 4½ ft. base alongside.</p> <p>Land; rolling.</p> <p>Soil; 2nd rate.</p> <p>Cottonwood and sumach in Creek bottom.</p> <p style="text-align: right;">July 19, 1887.</p>	+200
	General Description.	
	<p>The greater portion of this Tp. is rough and mountainous interspersed with deep canyons. There is a scattering growth of pine and fir timber, and also some pine and bunch grass.</p> <p>The soil, being 3rd and 4th rate. On the table land, extending through Secs. 15, 21, 22 and 28, the soil is good 2nd rate and produces a fine growth of bunch grass. and sunflowers.</p>	