

Subdivisional Lines T. 1 S., R. 33 E., W.M.

| Chains | Feet |
|--|-----------------|
| <p>In the northern part of the Tp. the lands along the McKay Creek are well adapted to farming purposes, with 1st rate soil. Considerable improvements have already been made along this Creek by the Indians.</p> | |
| <p>Subdivisions of T. 1 S., R. 33 E., W.M. As surveyed by John C. Arnold, U.S. Deputy Surveyor, Under Contract No. 551 Dated Mar. 19, 1890.</p> | |
| <p>I commence at the Closing Cor. to Secs. 16 & 17, on Reservation Bdy., which is a basalt stone, 12 x 10 x 8 ins. in small mound of stone and marked U.R.C.C. I repair stone mound, leaving it 3 ft. high by $4\frac{1}{2}$ ft. base. I run, thence, descend.</p> | |
| | Var. 21° 00' E. |
| S. bet. Secs. 16 & 17. | |
| <p>4.34 Set basalt stone, 12 x 10 x 6 ins., 8 ins. in-ground for Cor. to Secs. 16, 17, 20 & 21, marked, 4 notches on E. face, and 3 notches on S. face. Raised mound of stone 2 ft. high, $4\frac{1}{2}$ ft. base about the Cor. on a stony hill side facing S.W. Pits impracticable.</p> | |
| Land; mountainous, 4.34 chs. | |
| Soil; stony 5th rate. No timber. | |
| Lat. by my instrument N. 45° 28'. | |
| E. on a random line bet. Secs. 16 & 21. | |
| | Var. 21° 00' E. |
| Ascend. | |
| <p>4.47 Intersect N. & S. line, 1 lk. S. of Closing Cor. to Secs. 16 & 21 on Res. Bdy., which is a basalt stone, 10 x 9 x 8 ins., in stone mound and marked U.R.C.C. on E. face from which, I run, Descend.</p> | |
| S. 89° 52' W. on a true line bet. Secs. 16 & 21. | |
| | Var. 21° 00' E. |
| The Cor. to Secs. 16, 17, 20 & 21. | |
| Land; mountainous and stony, 4.47 chs. | |
| Soil; 5th rate. No timber. | |