

Subdivisions, Tp. 1 S., R.33 E., W.M.

Chains		Feet
	<p>E. on a random line bet. Secs. 21 & 28.</p> <p style="text-align: right;">Var. 21° 20' E.</p> <p>Descend steep hillside.</p>	
.75	Deep ravine, course N.W. Ascend 50°	
17.25	Intersect Res. Bdy., 82 lks. N. of Closing Cor. to Secs. 21 & 28, which is a basalt stone, 14 x 12 x 6 ins., in stone mound, marked U.R.C.C. on E. face.	
	<p>Note:</p> <p>I carefully retrace line bet. Secs. 28 & 29 and find the distance 48.61 chs. as above, the course of the line to be N. & S., and the random line, E. as given. The course of the line bet. Secs. 21 & 28, <u>will</u> therefore, be N.87° 17' W., commencing at Closing Cor. to Secs. 21 & 28, as above described,</p> <p>I run,</p> <p>N. 87° 17' W. on a true line bet. Secs. 21 & 28.</p> <p style="text-align: right;">Var. 19° 00' E.</p> <p>Descend.</p>	
16.50	Deep ravine, course N.W.; ascend.	
17.25	The Cor. to Secs. 20,21,28 & 29.	
	Land; mountainous,17.25 chs. No timber.	
	Soil; 3rd rate- Good grass.	
	<p>N. on a random line bet. Secs. 20 & 21</p> <p style="text-align: right;">Var. 21° 20' E.</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
78.07	Intersect E. & W. line, 65 lks. W. of Cor. to Secs. 16,17, 20 & 21.	
	Thence I run	
	S.0° 28' W. on true line bet. Secs. 20 & 21.	
	Var. 21° 00' E.	
	Ascend.	
12.50	Summit of ridge falls W. Descend.	
28.35	Deep ravine, course S.W. Ascend.	
33.50	Summit of ridge falls W. Descend.	
35.64	Ravine ,course S.W. Ascend.	